"ഭരണഭാഷ-മാതൃഭാഷ"

ചീഫ് എഞ്ചിനീയറുടെ കാര്യാലയം
തദ്ദേശസ്വയംഭരണ - ലോക്കൽ ഇൻഫ്രാസ്ട്രക്ചർ
ഡവലപ്മെന്റ്&എഞ്ചിനീയറിംഗ് വിംഗ്
റവന്യൂ കോംപ്ലക്സ്, മൂന്നാംനില
പബ്ലിക് ആഫീസ് ബിൽഡിംഗ്
തിരുവനന്തപുരം 33

Phone : 0471 – 2324951
0471 – 2325071
Tele Fax : 0471 – 2324951
Email: celsgd@gmail.com
Website : www.celsgd.kerala.gov.in

നം. ഡിബി.1/9286/17/സിഇ/എൽ.ഐ.ഡി&ഇ.ഡബ്ല്യു

തീയതി: 04/12/2021

സർക്കുലർ

വിഷയം:- തദ്ദേശസ്വയംഭരണ വകുപ്പ് - എൽ.ഐ.ഡി&ഇ.ഡബ്ല്യു - ക്വാളിറ്റി കൺട്രോൾ ലബോറട്ടറികളിലെ ഉപകരണങ്ങളുടെ ഡാറ്റാ ബേസ് തയ്യാറാക്കുന്നത് - സംബന്ധിച്ച്

സൂചന:- തദ്ദേശസ്വയംഭരണ വകുപ്പ് ചീഫ് എഞ്ചിനീയറുടെ 21/11/2019, 18/12/2020 എന്നീ തീയതികളിലെ ഇതേ നമ്പർ ഉത്തരവുകൾ

*****

തദ്ദേശസ്വയംഭരണ വകുപ്പ് എഞ്ചിനീയറിംഗ് വിഭാഗത്തിൽ, എല്ലാ ജില്ലാ പഞ്ചായത്തുകളിലും തിരഞ്ഞെടുക്കപ്പെട്ട ബ്ലോക്ക് പഞ്ചായത്തുകളിലും, സംസ്ഥാന ബഡ്ജറ്റ് പ്ലാൻ വിഹിതത്തിൽ നിന്നും തുക അനുവദിച്ച് ഗുണമേൻമ പരിശോധന ഉപകരണങ്ങൾ വാങ്ങി, ക്വാളിറ്റി കൺട്രോൾ ലാബുകൾ സജ്ജീകരിക്കുന്നതിന് സൂചന പ്രകാരം തുക അനുവദിച്ച് ഉത്തരവായിട്ടുള്ളതാണ്. ആയത് പ്രകാരം ജില്ലാ പഞ്ചായത്തുകളിലും, തിരഞ്ഞെടുക്കപ്പെട്ട ബ്ലോക്ക് പഞ്ചായത്തുകളിലും ഉപകരണങ്ങൾ വാങ്ങിച്ചിട്ടുള്ളതാകുന്നു. ക്വാളിറ്റി കൺട്രോൾ ലാബുകളുടെ പ്രവർത്തനം മെച്ചപ്പെടുത്തുന്നതിന്റെ ഭാഗമായി ഇത്തരത്തിൽ വാങ്ങിയ ഉപകരണങ്ങളുടെ ഒരു ഡാറ്റാ ബേസ് തയ്യാറാക്കേണ്ടത് അത്യന്താപേക്ഷിതമാണ്. തിരഞ്ഞെടുക്കപ്പെട്ട ബ്ലോക്ക് പഞ്ചായത്തുകളുടെ വിവരങ്ങൾ ഇതോടൊപ്പം അനുബന്ധമായി ചേർത്തിട്ടുള്ള സൂചന ഉത്തരവിൽ പരാമർശിച്ചിട്ടുണ്ട്. ആയതിനാൽ, ഡാറ്റാ ബേസിൽ വിവരങ്ങൾ ചേർക്കുന്നതിലേക്കായി **P-1131** എന്ന പ്രൊഫോർമയിൽ എല്ലാ ജില്ലാ പഞ്ചായത്തുകളും, തിരഞ്ഞെടുക്കപ്പെട്ട ബ്ലോക്ക് പഞ്ചായത്തുകളും ലഭ്യമായ ഉപകരണങ്ങളുടെ വിവരങ്ങൾ **08/12/2021 ന് 3.00 മണിക്ക്** മുമ്പായി രേഖപ്പെടുത്തേണ്ടതാണ് എന്ന് നിർദ്ദേശിക്കുന്നു.

പ്രൊഫോർമയിൽ ഉൾപ്പെടാത്ത ഉപകരണങ്ങൾ വാങ്ങിയിട്ടുണ്ടെങ്കിൽ, താഴെയുള്ള വരിയിൽ ഉപകരണങ്ങളുടെ പേര് രേഖപ്പെടുത്തി, തൊട്ടടുത്ത കോളത്തിൽ ലഭ്യമായ ഉപകരണങ്ങളുടെ എണ്ണം പൂരിപ്പിക്കുകയും ചെയ്യേണ്ടതാണ്.

Link to pro-forma P-1131

ചീഫ് എഞ്ചിനീയർ

എൻ.പി/-

PROCEEDINGS OF THE CHIEF ENGINEER LOCAL SELF GOVERNMENT DEPARTMENT, THIRUVANANAPURAM

(Present : Rajan.M.V)

Sub:- LSGD-Budget allocation for the financial year 2019-20 – Setting up of Quality Control Laboratories at Sub Division Offices –Reg.

Read:- G.O (Rt)1929/2019/LSGD dated 05.09.2019

ORDER No.DB1/9286/17/CE/LSGD Dated 21.11.2019

Vide G.O cited, Government accorded Administration Sanction for Rs.30.24 Lakhs, allocated in the State budget 2019-20 for Setting up of Quality Control Laboratories at Sub Division Offices. It is proposed to set up Laboratories two each at Thiruvananthapuram, Malappuram Districts and one each at remaining 12 districts. The type of instruments, it's specification, minimum number of quanties along with name of Sub-Divisional offices (Block Panchayats) selected in each district is as per the table given below.

Table 1

Sl.No.	Item	Specification	Quanity
1	IS Sieves (GI) with Lid & Pan	90mm, 63mm, 45mm,26.5mm,22.4mm, 13.2mm,11.2mm, 5.6mm	1 set
2	IS sieves (Brass body) with Lid & Pan	4.75mm, 2.36mm,75 microns	1 set
3.	Electronic Weighing Balance	Least count-10mg, Capacity 60kg	1 nos
4	Concrete Cube Mould	15X15X15cm steel	9 nos
5	Digital Thermometer	-	3 nos
6	Digital Micrometer (Electronic Screw Gauge)	Stainless steel 19x10x5cm	2 nos
7	Digital Vernier Calipers	With large LCD display handy conversion table	1 nos
8	Concrete Compression Testing Machine	Manually operated	1 nos
9	Automatic Level with staff & accessories	Sokkia/Leica length 215mm magnification – 24x Level accurate -2mm Resoling -4" Ojective aperture -32mm Levelling staff -Aluminum4m Telescopic water proof canvas cover - 4 Sec Closed Length 1215mm Gradation 5mm in front & 1mm back Width 5mm, thickness 27mm Weight – 1.6kg	1 set

Table 2

Sl.No.	District	Name of Block Panchayat Selected
1	Thiruvananthapuram	Athiyannoor, Kilimanoor
2	Kollam	Kottarakkara
3	Pathanamthitta	Koippuram
4	Alappuzha	Mavelikkara
5	Kottayam	Uzhavoor
6	Idukki	Kattappana
7	Ernakulam	Muvattupuzha
8	Thrissur	Vadakkancherry
9	Palakkad	Pattambi
10	Malappuram	Thirur, Malappuram
11	Kozhikkode	Kunnamangalam
12	Wayanad	Sulthan Bathery
13	Kannur	Koothuparambu
14	Kasargod	Kanhangad

As per this, Setting up of Quality Control Laboratories at Block Panchayats are to be completed by 31.12.2019. In the above circumstances, Assistant Executive Engineers of concerned Block Panchayats are hereby authorized to implement the work as per type, quantity, specification and time specified above at an estimate cost of 1,80,000/-. Store purchase manual should be scrupulously followed in all cases of purchase. Allotment will be made from this office on production of the actual bill of the instrument procured.

CHIEF ENGINEER

Copy to :-1. Assistant Executive Engineers of concerned Block Panchayats
2. Executive Engineers of all District Panchayats

ലോക്കൽ ഇൻഫ്രാസ്ട്രക്ചർ ഡവലപ്മെന്റ് & എഞ്ചിനീയറിംഗ് വിംഗ്
ചീഫ് എഞ്ചിനീയറുടെ കാര്യാലയം
ചീഫ് എഞ്ചിനീയറുടെ നടപടിക്രമങ്ങൾ
[ഹാജർ: ശ്രീ. കെ ജോൺസൺ, ചീഫ് എഞ്ചിനീയർ]

വിഷയം :- തദ്ദേശസ്വയംഭരണ വകുപ്പ് - ലോക്കൽ ഇൻഫ്രാസ്ട്രക്ചർ ഡവലപ്മെന്റ് & എഞ്ചിനീയറിംഗ് വിഭാഗം – പദ്ധതി വിഹിതം 2020-21 സബ് ഡിവിഷനുകളിൽ ക്വാളിറ്റി കൺട്രോൾ ലാബുകൾ സ്ഥാപിക്കുന്നത് – അനുമതി നൽകി ഉത്തരവാകുന്നു.

സൂചന :- ജി.ഒ (ആർ.റ്റി) നം. 1516/2020/എൽ.എസ്.ജി.ഡി, തീയതി 14/08/2020

ഉത്തരവ് നമ്പർ. ഡിബി1/9286/17/സിഇ/എൽ.ഐ.ഡി&ഇ.ഡബ്ല്യു.
തീയതി, 18/12/2020

സൂചന ഉത്തരവ് പ്രകാരം സംസ്ഥാന ബഡ്ജറ്റ് 2020-21 പ്ലാൻ വിഹിതമായി 225 ലക്ഷം രൂപ ലഭ്യമായിട്ടുണ്ട്. ആയതിൽ 24.20 ലക്ഷം രൂപ ലോക്കൽ ഇൻഫ്രാസ്ട്രക്ചർ ഡവലപ്മെന്റ് & എഞ്ചിനീയറിംഗ് വിഭാഗത്തിലെ 9 ബ്ലോക്ക് പഞ്ചായത്തുകളിൽ ക്വാളിറ്റി കൺട്രോൾ ലാബുകൾക്ക് ആവശ്യമായ ചുവടെ പറയുന്ന ഉപകരണങ്ങളും (പരമാവധി 1.80 ലക്ഷം രൂപ വരുന്ന), തിരുവനന്തപുരം ജില്ലാ പഞ്ചായത്തിൽ ഒരു യൂണിവേഴ്സൽ ടെസ്റ്റിംഗ് മെഷീനും (പരമാവധി 8 ലക്ഷം രൂപ വരുന്ന) വാങ്ങുവാൻ നിശ്ചയിച്ചിട്ടുണ്ട്. വാങ്ങൽ നടത്തേണ്ട ലാബ് ഉപകരണങ്ങൾ സംബന്ധിച്ച പട്ടിക, സബ് ഡിവിഷനുകളുടെ പേര് എന്നിവ ചുവടെ ചേർക്കുന്നു.

I. **One Universal Testing Machine (UTM) at Thiruvananthapuram District Panchayath**

II.

Sl. No	Item	Specification	Quantity
1	IS Sieves (GI) with Lid & Pan	90mm, 63mm, 45mm,26.5mm,22.4mm, 13.2mm,11.2mm, 5.6mm	1 set
2	IS sieves (Brass body) with Lid & Pan	4.75mm, 2.36mm,75 microns	1 set
3	Electronic Weighing Balance	Least count-10mg, Capacity 60kg	1 nos
4	Concrete Cube Mould	15X15X15cm steel	9 nos
5	Digital Thermometer	-	3 nos
6	Digital Micrometer (Electronic Screw Gauge)	Stainless steel 19x10x5cm	2 nos
7	Digital Vernier Calipers	With large LCD display handy conversion table	1 nos
8	Concrete Compression Testing Machine	Manually operated	1 nos

9	Automatic Level with staff & accessories	Sokkia/Leica, length 215mm magnification – 24x Level accurate -2mm, Resoling -4" Objective aperture -32mm ; Levelling staff -Aluminum4m Telescopic water proof canvas cover -4 Sec Closed Length 1215mm Gradation 5mm in front & 1mm back Width 5mm, thickness 27mm Weight – 1.6kg	1 set

List of 9 Block Panchayaths for Supply of Lab Equipments

Sl.No.	District	Name of Block Panchayat Selected
1	Kollam	Sasthamcotta
2	Alappuzha	Pattanakkad
3	Kottayam	Vaikom
4	Idukki	Idukki
5	Ernakulam	Mulamthuruthy
6	Thrissur	Irinjalakkuda
7	Palakkad	Palakkad Municipality
8	Kozhikkode	Vadakara
9	Kasargod	Manjeswaram

ബന്ധപ്പെട്ട അസിസ്റ്റന്റ് എക്സിക്യൂട്ടീവ് എഞ്ചിനീയർമാർ/എക്സിക്യൂട്ടീവ് എഞ്ചിനീയർ സ്റ്റോർ പർച്ചേസ് മാനദണ്ഡങ്ങൾക്ക് വിധേയമായി ഉപകരണങ്ങൾ വാങ്ങേണ്ടതാണ്. നടപടി ക്രമങ്ങൾ പാലിച്ച് ബില്ലും, അനുബന്ധ രേഖകളും ജില്ലാ പഞ്ചായത്ത് എക്സിക്യൂട്ടീവ് എഞ്ചിനീയർ സമർപ്പിക്കുന്ന മുറയ്ക്ക് അലോട്ട്മെന്റ് ലഭ്യമാക്കുന്നതാണ്.

വിശ്വസ്തതയോടെ,

ചീഫ് എഞ്ചിനീയർ

പകർപ്പ്:- ബന്ധപ്പെട്ട ഉദ്യോഗസ്ഥർക്ക്

എൻ.പി/-